



**SECTION**

- NOTES: 1. LOCATE VENT BOXES AS FOLLOWS:  
 A. AT EVERY HIGH POINT IN THE CHILLED WATER SYSTEM.  
 B. AS REQUIRED TO VENT NEW SECTION OF LOOP PIPING DURING INITIAL FILL AND TEST.

REV	DATE
0	12/22/02
1	2/9/2016
2	8/26/2021
DRAWN BY: BB	
CHECKED BY: TG	

Construction Standard  
 CW Vent Box Detail

Energy Management  
 Campus Facilities  
 UNIVERSITY OF MISSOURI—COLUMBIA



DRAWING NOT TO SCALE  
 DATE: 2/9/2016